



**SHRI MATA VAISHNO DEVI SHRINE BOARD, KATRA
TENDER DOCUMENT**

FOR

Renovation of main Bhojanalya, prefab structure for the installing Dumbwaiter in Bhojanalya Building and Re-wiring of Bhojanalya at Adhkuwari.

e-NIT No.: CO/DEV/703/220 DATED: 07.04.2026

**Last Date for submission of e-Tender : 24.04.2026
upto 3:00 PM**

Address: Central Office, Shri Mata Vaishno Devi Shrine Board, Katra (J&K) – 182301
Ph.: 01991-232075, 234570, **Fax:** 01991-232120, 232089

E-mail: dyceo@maavaishnodevi.net, am.dev@maavaishnodevi.net

Website: www.maavaishnodevi.org, www.jktenders.gov.in



Office of the Chief Executive Officer Shri Mata Vaishno Devi Shrine Board, Katra

e-NIT No.: CO/Dev/703/220

Dated: 07.04.2026

E-Tenders on prescribed format are invited **on percentage basis** on behalf of Shri Mata Vaishno Devi Shrine Board through Chief Executive Officer, SMVDSB, under two bids system from reputed and experienced Firms / Contractors / Agencies registered with Govt. Organizations/ Semi Govt. Organizations and Public Sector Undertakings for the following work:

S. No	Description of work	Approx. cost of work	Time of completion	Amount of EMD
1	Renovation of main Bhojanalya, prefab structure for the installing Dumbwaiter in Bhojanalya Building and Re-Wiring of Bhojanalya at Adhkuwari.	Rs. 58,94,329.13/-	60 days	Rs. 1,17,887/-

The e-NIT consisting of detailed Terms & Conditions, Eligibility Criteria and other details can be seen / downloaded from <http://jktenders.gov.in> and/or SMVDSB website www.maavaishnodevi.org

The Tender Fee of **Rs. 1000/-** and the Earnest Money Deposit for the above-mentioned amount can be deposited in the official account of Shri Mata Vaishno Devi Shrine Board, Branch - **J&K Bank Katra, Account No. 0235040500001804, IFSC – JAKA0KATTRA** The bidder shall mention EMD details and UTR No. in the prescribed Technical Bid but not in the shape of Demand Draft (DD).

The complete bidding process will be done online on the e-Tender portal www.jktenders.gov.in. The tenders must be submitted strictly in accordance with the provisions of the detailed e-NIT. **No Proposal will be accepted through any other mode.**

Sd/-
(Pawan Kumar Goswami, JKAS)
Dy. Chief Executive Officer

1. INSTRUCTIONS TO BIDDERS REGARDING E-TENDERING PROCESS

- i. The interested bidders can download the e-NIT/ bidding document from the website www.jktenders.gov.in /official website of SMVDSB www.maavaishnodevi.org.
- ii. To participate in the bidding process, bidders have to get (DSC) “Digital Signature Certificate” as per information Technology Act-2000. This certificate will be required for digitally signing the bid.
- iii. The Bidders, who already possess valid (DSC) Digital Signature Certificate, need not procure a new Digital Signature Certificate.
- iv. The Technical Bids shall be opened online as per the scheduled date & time mentioned in the e-NIT document.
- v. Financial Bids of technically qualified bidders shall be opened online, date and time for which shall be communicated to them separately.
- vi. The bidders have to submit their bids online in electronic format with Digital Signature. The bids cannot be uploaded without Digital Signature. No Proposal will be accepted in physical form.
- vii. Before submission of online bids, bidders must ensure that scanned copies of all the necessary documents as mentioned in the e-NIT have been attached with the bid.
- viii. Bidders are advised to use “My Documents” area in their user on <http://jktenders.gov.in>, e-tendering portal to store important documents like Balance sheet, GST Registration Certificate, IT certificate and other related documents etc., and attach these certificates as Non-Statutory documents while submitting their bids.
- ix. Bidders are advised not to make any change in BOQ (Bill of Quantities) contents or its name. In no case, they should attempt to create a similar BOQ of their own manually. The BOQ downloaded should be used for filling the item rate as prescribed and it should be saved with the same contents.
- x. Bidders are advised to scan their documents at 100 DPI (Dots per Inch) resolutions with Black and White, PDF / Scan properly.
- xi. The Bidders should carefully study the e-NIT document and prepare their tender with consideration of all provisions of the document. They should fully acquaint themselves **with site conditions** and all other factors which may influence the preparation of his tender.
- xii. Any queries / information related to the tender document / work can be sought via e-mail at dyceo@maavaishnodevi.net and am.dev@maavaishnodevi.net.

2. TENDER SCHEDULE:

- i. The e-NIT Schedule is as under:

Publishing Date	:	07.04.2026 at 03:00 PM
Download Start Date	:	07.04.2026 at 03:30 PM
Pre-Bid Meeting Date	:	15.04.2026 at 04:00 PM
Bid Submission Start Date	:	16.04.2026 at 04:00 PM
Bid Submission End Date (online)	:	25.04.2026 at 03:00 PM
Date of Opening of Technical Bid (online)	:	27.04.2026 at 03:00 PM

- ii. In case of holiday, the bids will be opened on the next working day. Further, the price bids of only those bidders shall be opened who qualify the Technical Eligibility Criteria after scrutiny of the documents in Technical Bid, which shall be notified separately.
- iii. SMVDSB, will not be responsible for any delay in online submission of the bid due to any reason (Technical or otherwise).
- iv. Bidders must ensure to upload scanned copies of all necessary documents as mentioned in the e-NIT.
- v. The bidders need not to submit hard copies of the uploaded documents at Central Office, SMVDSB, Katra, which shall only be obtained from the bidder who is declared as the lowest after the opening of the Financial Bids. **However, the original EMDs shall reach Central Office, SMVDSB, Katra within a week's time from the last date of bids submission.**

3. TECHNICAL ELIGIBILITY CRITERIA

- i. The **Average Annual Financial Turnover** of the Bidder during the last 03 consecutive Financial Years, ending 31st March of the previous financial year should be at least **60% of the value of the project (FY 2022-23, 2023-24 & 2024-25)**.
- ii) The Bidder must have **experience** of having successfully completed similar nature of works with Govt. or Semi-Govt. Departments / Govt. PSU's / Autonomous Bodies, during last **05 years** ending last day of month previous to the one in which tenders are invited as follows:
- 03 (Three) similar** completed works costing not less than 40% of the estimated cost.
- Or
- 02 (Two) similar** completed works costing not less than 50% of the estimated cost.
- Or
- 01 (One) similar** completed work costing not less than 80% of the estimated cost.

****Similar nature of work means the works related to the construction / Repair and Renovation of buildings including electrification & plumbing works.**

(Certificate to this effect to be issued by an officer, not below the rank of Executive Engineer or equivalent).

4. SUBMISSION OF TENDERS:

The tenderers are required to submit their tender under 2 bids system with Cover-I (Technical Bid Qualification) and Cover-II (Price Bid).

a. Cover-I (Technical Bid Qualification):

This cover shall contain scanned copies of the following:

- i.** Proof of Tender fee and EMD deposited with the SMVDSB.
- ii.** Copies of original documents defining the constitution or legal status, place of registration and principal place of business.
- iii.** Financial turnover Certificate, year-wise, for the last three Financial Years **i.e. FY 2022-23, 2023-24 & 2024-25**, duly certified by the Chartered Accountant with UDIN number.
- iv.** Work Completion Certificates along with Letter of Awards of having executed and completed successfully works of similar nature as defined under Clause 3 of the Technical Eligibility Criteria, in any Govt. or Semi-Govt. Departments / Govt. PSU's / Autonomous Bodies during the last five years, duly issued by an officer, not below the rank of Executive Engineer or equivalent.
- v.** Copy of PAN Card and GST registration certificate and valid Contractor Registration Card issued from the Competent Authority.
- vi.** Reports on the financial standing of the bidder such as profit and loss statement, balance sheet for the last three Financial Years **i.e FY 2022-23, 2023-24 & 2024-25** duly certified by Chartered Accountant with UDIN number and supported with ITRs of the last three Financial Years.
- vii.** Bidder shall furnish proof of the latest returns in GST-3/GSTR-3B.
- viii.** Signed and Stamped copy of Tender document (all pages) in respect of acceptance of all terms and conditions of e-NIT.

Note: Original documents if required to be verified, the same shall have to be facilitated by the bidder.

b. Cover II (Price Bids):

- i. Price bid shall contain price quoted as per BOQs enclosed & is to be submitted online in the form of BOQ only as per **Annexure – A and B**.
- ii. Price Bids shall be opened of only those tenderers who have qualified the Technical Eligibility Criteria.
- iii. The price bid should be absolute and unconditional.

5. BILL OF QUANTITIES

- i. The Bill of quantities is enclosed as **Annexure – A and B** for reference purpose. The online BOQ contains all the annexure i.e. A & B.
- ii. The quantities given in the Bill of quantities are tentative and provisional, and are given to provide a common basis for bidding. The basis of payment shall be as per the actual quantities of work ordered and executed, as measured and verified by the Engineer In-charge, SMVDSB and valued at the rates in the bill of quantities.
- iii. The advertised quantities overall may increase or decrease up to 25% for which the bidder shall have to execute the extra quantities over the advertised quantities at the same rates. For the items executed lesser than the advertised quantities, actual payment of work executed shall be made.
- iv. SMVDSB, reserves the right to delete, add/modify any item of work during the operation of the work. The contractor shall have no claim on account of any such act.
- v. The Contractor shall be bound to execute extra items of works as directed by the Engineer In-Charge, SMVDSB.
- vi. The rates and prices in the bill of quantities shall, except as otherwise provided under the Contract, include all required equipments including labour, sundries, T&P, supervision, erection, maintenance during execution, insurance, profit, taxes and duties, packing and forwarding, loading and unloading, head Loads, together with all general risks, liabilities, and obligations set out or implied in the contract including the cost of remedying defects.
- vii. The cost of temporary works, if any like dewatering and drainage arrangements, establishment and maintenance of contractor's office and stores, watch and ward of site including workshop and stores, implementation of all safety procedures. Implementation of Environment related issues etc shall be part of work and shall not be paid extra.
- viii. The method of measurement of completed work for payment shall be accorded with relevant specifications and code practice.

- ix. No escalation shall be paid during the contract period for completion of the work on the quoted rates or even during the extended period

6. SPECIAL CONDITIONS

- i. **VARIATIONS:** The advertised quantities of overall items may increase or decrease up to 25% for which the contractor shall have to execute, if any, the extra quantities over the advertised quantities at the same rates. Similarly, if the items executed are lesser than the advertised quantities, actual payment of work executed shall be made. In case the variation in quantities exceeds 10% of the total cost, the variation and the cost implication shall be got approved from the competent authority by the Engineer-In-Charge.
- i. **Extra Item:** Items not covered in the advertised rate list but found necessary during execution of work at the site, the same shall be paid on the basis of J&K SOR, 2022 and if not covered in the advertised rate list / J&K SOR, 2022 the same shall be paid on the basis of analysis of rates duly prepared / verified by the concerned Engineering-in-charge on the Lowest Market Rates prevalent in the market. Items not covered in the advertised rate list but found necessary during execution of work at the site, the same shall be paid on the basis of J&K SOR 2022 as per appreciation / depreciation.
- ii. **Shifting of items from the Main Bhojanalya to any other suitable location:** Nothing shall be paid for shifting of goods & material including items belonging to the Bhojanalya to any other suitable location and back to the Bhojanalya after completion of the renovation work.
- iii. **Tools & Plants (T&P)** required for the work shall be arranged by the Contractor.
- iv. The Shuttering material required for the work shall be in the scope of the contractor.

7. CORRECTION OF ERRORS

- i. If there be a discrepancy between the unit price and the total price that is obtained by multiplying the unit price & quantity, the unit price shall prevail and total price shall be corrected.
- ii. If there be a discrepancy in figure and word the total amount stated in word shall prevail.

8. BID SUBMISSION / WITHDRAWAL

- i. Bids shall be submitted online within the stipulated deadline. SMVDSB, may at its discretion, extend the deadline of bid submission by issuing an amendment. In that case all rights and obligations of SMVDSB, and the bidders previously subject to the original deadline shall thereafter be subject to the new deadline as extended.

- ii. No bid shall be withdrawn by any of the participating tenderers. Withdrawal of bid after its submission shall result into forfeiture of EMD.

9. BIDDER'S SITE VISIT

J&K SOR, 2022 allow carriages, lead & lift for building materials from the source of supply to the site of work but in this contract nothing extra shall be paid on account of lead, Head Load, lift & carriages etc. The contractors/firms are therefore required to visit the site of work and quote their rates accordingly. Such site visit shall be at the bidder's own expense, risk and responsibility. Lack of knowledge of site /site conditions/working conditions shall not be considered as a reason whatsoever it may be. SMVDSB, shall however, facilitate such visits to the extent possible on written requests of prospective bidders.

10. COST OF BIDDING

The bidder shall bear all costs associated with the preparation and submission of his bid and SMVDSB in no case shall be responsible or liable for these costs, regardless of the conduct or outcome of the bidding process.

11. GENERAL CONDITIONS

- i. Tender without copy of requisite tender fee and in deficient of any conditions of e-NIT or submitted incomplete in any respect is liable to be rejected.
- ii. Conditional Tenders shall not be accepted and shall be outrightly rejected.
- iii. The Tender Fee is non-refundable.
- iv. Each Bidder shall have to submit only one Tender; submission of any additional Tender shall invite disqualification.
- v. The Tender offer shall be valid for **90 days** from the last day of receiving of the tender. However, prior to expiry of the original Validity Period, SMVDSB may, on the merit of case, request for extension of validity of the offer for a further period of maximum **30 (thirty) days** without any change in terms & conditions of the offer.
- vi. Even though any Bidder may satisfy the requirements of e-NIT, he/she would be liable for disqualification on grounds of submitting misleading / false information or deliberately suppressing the information in the forms, statement and enclosures in the Eligibility Criteria document and have record of poor performance such as abandoning work, leaving Contract incomplete or financial failures / weaknesses etc.
- vii. If any information furnished by the contractor is found incorrect at any stage, Contract shall be terminated and further penal action shall be initiated e.g. forfeiture of EMD / Performance Security / Security Deposit and debarring for period of three years for participating in SMVDSB tender process.
- viii. The contract as a whole or part thereof is Non-Transferable.
- ix. SMVDSB reserves the right to instruct the bidders to submit hard copy of any relevant document (and to produce the original documents for verification) during scrutiny & evaluation of bids. Bidders' failure to comply to such instruction may lead to rejection of bid.
- x. The Bidder shall comply with all the statutory provisions as laid down under various Laws/Act/Rules like Employees Provident Fund, ESI and other Laws/Acts/Rules in force from time to time.

- xi.** The contractor shall be under obligation to comply with all statutory / labour laws / regulations in vogue.
- xii.** The contractor shall have to execute the job under strict supervision and to the best satisfaction of Engineer In-charge, SMVDSB.
- xiii.** SMVDSB reserves the right to accept or reject the bid, wholly or partly, or to split the work in parts and to add/delete any of the items, without assigning any reason whatsoever.
- xiv.** In case of any dispute or clarification in Tender, the decision of the Chief Executive Officer, SMVDSB shall be final & binding upon the Bidder.
- xv.** The contractor is bound to adhere to traffic regulations as is applicable from time to time and ensure arrangements of smooth regulation of traffic during execution of work.
- xvi.** The contractor shall not assign, sublet, or apportion the whole or any part of the contract, if found so the contract shall be terminated with immediate effect and suitable penalty shall be imposed.
- xvii.** The contractor must maintain a valid workers compensation insurance policy covering all their employees engaged in the project, ensuring adequate financial protection against work-related injuries or accidents, and must provide proof of such coverage to the project owner upon request.

12. EARNEST MONEY DEPOSIT (EMD) / BID SECURITY

- i.** The bidders shall have to deposit the requisite earnest money amounting to **Rs. 1,17,887/-**, in the official account of Shri Mata Vaishno Devi Shrine Board, Branch - **J&K Bank Katra, Account No. 0235040500001804, IFSC – JAKA0KATTRA** or it can be in the shape of CDR/TDR/FDR drawn from any nationalized/scheduled bank pledged to FA/Chief Accounts Officer, SMVDSB, Katra but not in the shape of Demand Draft (DD).
- ii.** Bid securities of the unsuccessful bidders shall be returned/released at the earliest after the expiry of the final bid validity period and latest by the **30th day** after the award of the contract to the successful bidder. Bid security shall be refunded to the successful bidder on receipt of performance security.
- iii.** The Earnest Money Deposit (EMD) of the successful bidder shall be released on deposit of performance security.
- iv.** A bidder's EMD will be forfeited if the bidder:
 - a.** Withdraws or amends his tender;
 - b.** Impairs or derogates from the tender in any respect within the period of the validity of the tender;
 - c.** If the bidder does not accept the correction of his bid price during evaluation and;
 - d.** If the tenderer fails to furnish the required performance security within the specified period.

13. ALLOTMENT OF WORK

- i)** **The work shall be allotted to the lowest bidder (L-1) quoting lowest price in the total price bid.**

- ii) After scrutiny and evaluation of Financial Bid, the Contract will be awarded to the Lowest Bidder and the successful bidder shall have to enter into an Agreement with the Shrine Board within a period of **14 days** from the date of award of the Contract.

14. PERFORMANCE SECURITY

- i. The successful Bidder shall furnish performance security equivalent to **05% (five percent)** of the total value of the Contract, in the form of Bank Guarantee from any Nationalized / Scheduled Bank pledged to the FA/Chief Accounts Officer, SMVDSB, Katra within a period of **07 Days** from the issuance of Letter of Award. Failure to do so within the stipulated period, the contract shall be liable for cancellation together with forfeiture of the Earnest Money Deposit (EMD).
- ii. The performance security shall be released on completion of Defect Liability Period on certification of Engineer In-charge, SMVDSB.

15. SECURITY DEPOSIT

- i. The Security Deposit equivalent to 05% shall be deducted from each running account bill and the same shall be released after completion of Defect Liability Period.
- ii. If the Contract price increases more than 10% of original contract value due to any reason, the contractor shall be under obligation to deposit the proportionately security amount within one weeks' time, falling which same shall be deducted from the bills raised by Contractor and kept as a security.

16. CONSTRUCTION PROGRAMME

The contractor shall submit a detailed construction/execution programme to the Engineer In-charge, SMVDSB within 5 days after the date of issue of LOA. The contractor shall also be required to submit a revised programme whenever the previous programme is inconsistent with actual progress explaining therein the reasons for the occurred delay.

17. MATERIAL

- i. The list of preferred makes of material for the work is enclosed at **Annexure - C and D**.
- ii. The material not mentioned in the list and to be used for the work shall have to be approved by the Engineer In-charge before using it at the site by the contractor.

18. TIME OF COMPLETION

The time of completion of the work in all respect shall be **60 days** reckoned from **7th day** from the date of issuance of letter of award.

19. EXTENSION OF TIME FOR COMPLETION

The contractor shall be entitled to an extension of time for completion if the work is delayed by any of the following causes:

- i. Additional items beyond the scope of work have been asked for execution.
- ii. A cause of delay attributable to Shrine Board.

If the contractor considers himself to be entitled to an extension of time for completion, the contractor shall within 15 days of the happening of that event, apply for the same to Engineer-In-Charge for determining such extension of time for approval from the competent authority. The request made after this period shall not be entertained for consideration of any such request for time extension. Time lost due to Monsoon rains/ winter rains shall not be considered for granting any time extension.

20. RATE OF PROGRESS

If at any time the progress of work is slow or the progress has fallen behind the timeline fixed, the contractor shall have to adopt measures like increase in labour or contractor's personnel/resources. The contractor shall not be entitled to claim any extra incurred cost on account of acceleration of work due to such measures. If the contractor fails to accelerate the progress, then the Engineer In-charge shall be entitled to increase resources from his end at the risk and cost of the contractor to accelerate the progress of works after serving a notice to the contractor.

21. PROGRESS REPORTS

The Contractor shall submit a weekly progress report to the Engineer In-charge in three copies. The first report shall cover the period up to the end of first calendar month following the commencement date. Reports shall be submitted on weekly basis thereafter, each within 7 days after the last day of the period to which it relates. The progress reports shall be accompanied with colour photographs in both soft and hard copies.

22. SUSPENSION OF WORK

The contractor shall not suspend work on his own unless otherwise directed by the Engineer In-Charge in writing.

23. TERMS OF PAYMENT

With a view to ensure expeditious completion of the work, the contractor shall be released part payment as under:

- i. Payment shall be made on running A/c bills for completed items after joint measurement of the work done (to be carried out by the contractor and the Engineer In-charge).
- ii. Final payment shall be done after successful completion of the work in all respects and to the entire satisfaction of the Engineer In-charge and its due handing over to the SMVDSB.

24. PENALTY FOR DELAYS

- i. If the contractor fails to complete the work within the specified time of completion, the penalty shall be imposed @0.5% (half percent) per week of contract value, subject to the maximum of 10% of the cost of the contract value shall be levied from contractor dues.
- ii. In case, the contractor fails to complete the work even after delaying the work beyond 04 weeks from the stipulated date of completion, Shrine Board reserves the right to get the remaining work executed at the risk and cost of the contractor. In addition, penal action in the shape of forfeiting of Performance Security, Security Deposit shall be taken against the contractor.

25. EMPLOYER'S TAKING OVER OF THE WORK

The Engineer In-Charge, SMVDSB shall, within 15 days after receiving the Contractor's application shall issue the taking over certificate to the contractor stating the date on which the works have been completed and defects, if any rectified. In case, the Engineer In-Charge is not satisfied with the completion then he will reject the application giving reasons and specifying the work required to be redone by the contractor to enable the taking over certificate to be issued. The contractor shall then complete this work before issuing a further notice. No part taking over of the works shall be allowed.

26. DEFECT LIABILITY PERIOD

The contractor shall be fully responsible for all the defects in respect of executed work for quality and workmanship including fixtures for a period of **02 year** from the date of completion of work. Any defect occurring in the work including electrical, sanitary and plumbing fittings and fixtures due to poor quality or workmanship during defect liability period shall be rectified / replaced by the contractor at its own cost. In case failure to do so within specified time frame, the SMVDSB, shall be at liberty to take up the rectification work at the risk and cost of the contractor and recover the cost on account of rectification from amount due to the contractor and in the shape of Security Deposit / Performance Security and balance payment due to the contractor.

27. TAXES, DUTIES AND OTHER LEVIES

- i. The contractor shall be solely responsible for the taxes that may be levied on the contractor/contractor's persons or on earnings of any of his office employee. The SMVDSB does not take any responsibility what-so-ever regarding taxes under Income Tax Act, for the contractor or his personnel. However as per the provisions of Income Tax Act, deduction of Income Tax for the executed work, at source shall be made by SMVDSB.
- ii. All other duties / levies payable by the bidder shall be included in the bid price and no claim on this behalf will be entertained by SMVDSB.
- iii. The price quoted in the BOQ shall be inclusive of all taxes and GST.

28. CONTRACTOR'S OPERATION AT SITE

The Contractor shall be responsible for keeping unauthorized persons off site. The contractor shall confine his operations to the site. During the execution of work, the contractor shall keep the site free from all unnecessary obstruction and shall clear away and remove from the site any scrap, wreckage, rubbish and temporary works which are no longer required.

29. REMEDIAL WORK

Notwithstanding any previous test or certification, the Engineer In-charge may instruct the contractor to:

- (a) Remove from site and replace any material which is not found as per specifications.
- (b) Remove and re-execute any work which is found defective and is not in accordance with the contract.
- (c) Execute any work which is urgently required for the safety of the works, whether because of an accident, unforeseen event or otherwise.

If the contractor fails to comply with the instruction within the reasonable time specified in the instructions, the Engineer In-charge, SMVDSB shall be entitled to employ and pay other persons to carry out the work and recover the cost from the contractor.

30. FOSSILS

All fossils, coins, articles of value or items of archaeological interest found on site during excavation or otherwise shall be handed over to the Engineer-In-Charge. It shall become the property of the owner.

31. QUALITY ASSURANCE /TESTING OF MATERIALS AND WORKS

The Contractor shall institute a quality assurance system to demonstrate compliance with the requirements of the contract.

Details of all procedures and compliance documents shall be submitted to the Engineer In-charge before each work commencement stage commences.

This clause shall also apply to all tests required to be done periodically or otherwise on materials and works. The contractor shall provide all assistance viz. Men and Material, consumables etc. to the Engineer In-charge or his representatives to carry out the tests efficiently. **The testing of materials shall be done in the Site laboratory set up by Shrine Board at SMVDIME, Kakryal. The tests for which the facility is not available in the site laboratory shall be got done from any other authorized laboratory as suggested by the Engineer In-charge. All such tests shall be done at contractor's expense.**

32. ELECTRICITY & WATER

Electricity and water for the work shall be in the Scope of Contractor. Further distribution shall be done by contractor at his own expenses and the cost of same shall be deemed to have been included in the rates. Electricity/Water for labour camp shall be arranged by contractor at his own expenses.

33. LABOUR

The contractor shall make his own arrangements for the engagement of all staff and labour, local or other, and make necessary arrangement for housing, feeding and transport at his own.

34. INDEMNITY

The contractor shall keep indemnified Shri Mata Vaishno Devi Shrine Board against all the losses, claims, injuries or damages to any persons or property which may arise out of or in consequences of this contract at its own cost.

35. CLEARANCE OF SITE

The contractor shall clear the site of the contractor's equipment, surplus material, wreckage, rubbish and temporary works from the site except that required to remedy notified defects, if any. In case the contractor fails to clear the site, the Engineer-In-Charge, SMVDSB shall remove those items from site of work at the risk and cost of the contractor.

36. CANCELLATION / TERMINATION OF THE CONTRACT IN FULL OR IN PART:

- a. If the contractor: -

- i. at any time makes default in proceeding with the works without due diligence and continues to do so even **7 days** after a notice in writing from the Engineer In-Charge, SMVDSB; or
- ii. commits defaults in complying with any of the terms and conditions of the contract and does not remedy it within **7 days** after a notice in writing is given to him in that behalf by the Engineer In-Charge, SMVDSB; or
- iii. fails to complete the works or any part of the work on or before the date of completion and does not complete them within the period specified in notice given in writing in that behalf by the Engineer In-Charge, SMVDSB; or
- iv. has obtained contract with the Shrine Board as a result of ring tendering or other non- bonafide methods of competitive tendering;

the Shrine Board shall outrightly cancel the contract by a written order to the contractor. In the event of cancellation, the contractors EMD / Performance Security / Security Deposit shall be forfeited.

b. The Shrine Board shall on such cancellation have powers to:

- i. If the work is not completed even after **7 days** after due date of completion, the Contract shall be terminated and work shall be executed as per the discretion of the Board including the option of offering the work to any other firm or inviting fresh tenders at the risk and cost of the Contractor with the penal cost to an extent of 20% cost of the unfinished works. The liquidated damages and penalty imposed shall be adjusted against this amount and balance, if any, shall be recovered from other dues (work done or deposit) of the Contractor.
- ii. Take possession of the site and any materials, machinery, equipments, stores, etc. thereon, and make out a list of such material in presence of the representative of the contractor who shall have to be present on one day notice and in case of non-compliance of the notice, measurements taken by the Shrine Board representative shall be considered as final and contractor will have no claim of any sort regarding this.
- iii. Carry out the incomplete work by any means at the risks and cost of the contractor.
- iv. On cancellation of the contract in full or in part, the Engineer In-Charge, SMVDSB shall determine what amount, if any, is recoverable from the contractor for completion of the works or in case the works or part of the works not to be completed, the loss or damage suffered by Shrine Board. In determining this amount, credit shall be given to the contractor for the value of the work executed by him up to the time of cancellation, the value of the contractor's materials taken over and incorporated in the work, and use of machinery belonging to the contractor.
- v. Any excess expenditure incurred or to be incurred by the Shrine Board in completing the works or part of the works or the excess loss or damage suffered or may be suffered by the Shrine Board as aforesaid after

allowing such credit shall be recovered from any amount due to the contractor on any account including forfeiting of Performance Security / Security Deposit and if such amount is not sufficient, the contractor shall be called upon in writing to pay the same, within 30 days of the notice given to that effect by the 'Engineer In-Charge'.

- vi. If the contractor fails to pay the required sum within the aforesaid period of 30 days, the Shrine Board shall have the right to sell any or all of the contractor's unused materials, machinery, implements, etc. and use the proceeds of sale thereof towards the satisfaction of any sums due from the contractor under the contract and in accordance with the provisions thereof.
- vii. Any sums in excess of the amounts due to the Shrine Board and unsold materials constructional plant, etc. shall be returned to the contractor, provided always that if cost or anticipated cost of completion by the Shrine Board, of the works is less than the amount which the contractor would have been paid had he completed the works, such benefit shall not accrue to the contractor.
- viii. Notwithstanding the above clause, the SMVDSB reserves the right to accept or reject any bid, and to cancel the bidding process and reject all bids, at any time prior to the award of contract, without thereby incurring any liability to the affected bidder or bidders or any obligation to inform the affected bidder or bidders of the grounds for SMVDSB action.

37. FORE CLOSURE OF THE CONTRACT

Foreclosure in full or in part due to abandonment or reduction in scope of work:

- i. If at any time after acceptance of the tender, Shrine Board decides to abandon or reduce the scope of the works for any reason whatsoever and hence not require the whole or any part of the works given to be carried out, the Engineer In-Charge shall give notice in writing to that effect to the contractor and the contractor shall have no claim to any payment of compensation or otherwise whatsoever, on account of any profit or advantage which he might have derived from the execution of the works in full, but which he did not derive in consequence of the foreclosure of the whole or part of the works.
- ii. The contractor shall be paid at contract rates full amounts for works executed at site duly certified by the Engineer In-Charge.

38. FORCE MAJEURE

If during the currency of contract, there is any outbreak of war, fire, major floods, earthquake, riots (other than among the contractor's employees) and similar other causes which whether financially or otherwise affects the execution of the Contract; the contractor unless contract is terminated under provision of this clause shall make his / her best efforts to complete the contract. However, after the outbreak of such war, Shri Mata Vaishno Devi Shrine Board shall be entitled to terminate the contract at any time by giving notice in writing. Force Majeure is hereby defined as a clause which is beyond

the control of SMVDSB / Contractor and which consequently affects the performance of the contract.

39. ARBITRATION

In case of any dispute arising between the parties to this e-tender and all matters connected therewith, both parties shall make every effort to resolve it amicably by direct informal negotiation. If even after thirty days from the commencement of informal negotiation, the parties have not been able to resolve the dispute amicably, then such disputes / differences shall be resolved by Arbitration as per the Arbitration and Conciliation Act, 1996.

- a) Either party may request other of its intention that a dispute be submitted to Arbitration and both the parties shall meet with 15 days from the date of receipt of such request to select a sole arbitrator mutually for the resolution of dispute and venue / seat or Arbitration shall be at Jammu / Katra / Reasi.
- b) In the event that the parties cannot agree upon the selection of the sole Arbitrator, either party or both the parties may move an application before the Hon'ble High Court at Jammu, under the Arbitration and Conciliation Act, 1996, for the appointment of sole Arbitration with seat / venue at Jammu for the resolution of dispute between the parties.

40. JURISDICTION

The Courts at Katra & Reasi alone shall have the jurisdiction with respect to the subject matter of the Contract.

Sd/-
(Pawan Kumar Goswami, JKAS)
Dy. Chief Executive Officer

No: CO/Dev/703/220
Dated: 07.04.2026



**Office of the Chief Executive Officer
Shri Mata Vaishno Devi Shrine Board, Katra**

**Bill of Quantities (Civil Works)
(Annexure-A)**

Subject: Renovation of Main Bhojanalya, Prefab Structure for the installing Dumbwaiter in Bhojanalya Building and Re-wiring of Bhojanalya at Adhkuwari.

S. No	Description	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1.	Dismantling door, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: Of area beyond 3 Sqm	NO.	23.00	390.50	8981.50/-
2.	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 meters lead. For thickness of tiles above 25 mm and upto 40 mm	SQM	794.28	89.95	71445.49/-
3.	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc including dismembering and stacking within 50 meters lead.	KG	2184.33	4.30	9392.62/-
4.	KOTA STONE FLOORING Kota stone slab flooring 25 mm thick over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing, polishing and curing complete with base of cement mortar 1:4 (1 cement : 4 Coarse sand)	SQM	286.25	1891.75	541513.43/-
5.	Providing and laying polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white	SQM	683.52	2336.45	15,97,010.30/-

	cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.				
6.	Providing edge moulding to 18 mm / 16 mm thick marble stone counters, Vanities etc. including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. Granite Work	MTR	150.63	381.70	57,495.47/-
7.	Brick work with common burnt clay (non-modular) bricks of class designation 7.5 in foundation and plinth including curing in: Cement mortar 1:6 (1 cement : 6 coarse sand)	CUM	5.70	7571.55	43,157.83/-
8.	Extra for brick work with common burnt clay bricks / cement concrete bricks in superstructure above plinth level upto floor five level.	CUM	5.70	1455.65	8,297.20/-
9.	CEMENT PLASTER (IN FINE SAND) 12 mm Cement plaster of mix: (1 cement : 4 fine sand)	SQM	39.03	283.80	11,076.71/-
10.	Providing and fixing of steel doors double revated with gauge shutter all complete including hinges, tower bolt, locker and necessary handle including fitting all carriage complete job (Make Tata or Rivazo)	NO.	11.00	34040.00	3,74,440/-/-
11.	Providing and fixing factory made UPVC white colour sliding glazed window upto 1.50 m in height dimension comprising of UPVC multi-chambered frame with in-built roller track and sash extruded profiles duly reinforced with 1.60±0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to UPVC profile), appropriate dimension of UPVC extruded glazing beads and UPVC extruded interlocks, DPDM gasket, wool pile, zinc alloy (white powder coated) touch locks with hook, zinc alloy body with single nylon rollers (weight bearing capacity to be	SQM	35.91	10083.65	3,62,103.87/-

	<p>40 kg), G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded to all corner, including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-charge. (Single / double glass panes, wire mesh and silicon sealant shall be paid separately).</p> <p>Note: For UPVC frame and sash extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable. Variation in this account shall be made.</p> <p>Three track three panels sliding window with fly proof SS wire mesh (Two nos. glazed & one no. wire mesh panels) made of (small series) frame 92 x 44 mm & sash 32 x 60 mm both having wall thickness of 1.9 ± 0.2 mm and single glazing bead of appropriate dimension (Area of window upto 1.75 sqm)</p>				
12.	Providing and fixing 5mm thick toughened glass in UPVC windows including all accessories with all carriage.	SQM	25.13	1560	39,202.80/-
13.	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes channels, plates etc. including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, including fixing the railing with necessary accessories and stainless steel dash fasteners, stainless bolts etc. of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be	KG	527.63	753.75	3,97,701.11/-

	considered excluding fixing accessories such as nuts, bolts, fasteners etc.).				
14.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade, one or more coats on old work.	KG	465.69	86.75	40,398.61/-
15.	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge: 1:3:6 or richer mix (i/c equivalent design mix)	CUM	21.99	1725.20	37,937.15/-
16.	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5, including getting out excavated earth and disposal of surplus excavated earth as directed: Ordinary Rock	CUM	3.06	924.80	2,829.89/-
17.	CEMENT CONCRETE (CAST-IN-SITU) Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centering and shuttering. All work upto plinth level with: 1:5:10 (1 Cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	CUM	2.55	4826.50	12307.58/-
18.	Providing and laying cement concrete in retaining walls, return walls, walls (Any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchors blocks, plain window sills, fillets etc. upto floor V level, including curing but excluding the cost of centring, shuttering and finishing with. 1:2:4 (1 Cement :2 coarse sand :4 graded stone aggregate 20 mm nominal size)	CUM	2.55	8422.45	21,477.25/-
19.	Cement concrete flooring 1:2:4 (1 Cement :2 coarse sand :4 graded stone aggregate) finished with a floating coat of neat cement including	SQM	13.38	562.15	7,521.57/-

	cement slurry and curing complete, but excluding the cost of nosing of steps etc complete.				
20.	Steel work in built up tubular (round, square or rectangular hollow tubes etc) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc complete. Hot finished welded type tubes.	KG	3552.63	156.95	5,57,585.28/-
21.	C.G.I SHEETS ROOFING Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal / vertical or curved surface) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required, 1.00 mm thick with zinc coating not less than 275 gram/m ²	SQM	13.38	1345.75	18,006.14/-
22.	Providing and fixing of 10 mm thick puff panel including channel, all accessories complete, carriages, lead and lift (complete job).	SQFT	1140.00	510.00	5,81,400/-
23.	Providing and fixing factory made UPVC white colour casement / casement cum fixed glazed windows comprising of UPVC multi-chambered frame, sash and mullion (hwhere ever required) extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to UPVC profile), UPVC extruded glazing beads of appropriate dimension, EPDM gasket, stainless steel (SS 304 grade) friction hinges, zinc alloy (White powder coated) casement handles, G>I fasteners 100 x 8 mm size for fixing frame to finished wall, plastic packers, plastic caps and	SQM	14.64	10800.25	1,58,115.66/-

	<p>necessary stainless steel screws etc. Profile of frame & sash shall be mitred cut and fusion welded at all corners, mullion (if required) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing sealant shall be paid separately)</p> <p>Note: For UPVC frame, sash and mullion extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable. Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made.</p> <p>Casement window double panels with S.S. friction hinges (350 x 19 x 1.9mm) made of (big series) frame 67 x 60 mm & sash / mullion 67 x 80 mm both having wall thickness of 2.3 ± 0.2 mm and single glazing bead / double glazing bead of appropriate dimension. (Area of window above 1.50 sqm)</p>				
24.	Providing and fixing 5 mm thick ACP sheet including rubble (Complete job).	SQM	133.88	120.00	16,065.6/-
25.	Providing and applying white cement based putty of specified thickness, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. 2 mm thick.	SQM	185.41	181.05	33,568.48/-
26.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade. Two or more coats on new work.	SQM	77.71	131.85	10,246.06/-
27.	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams / liter, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.	SQM	146.38	109.90	16,087.16/-
28.	Applying one coat of water thinnable	SQM	146.38	66.85	9,785.50/-/-

	cement primer of approved brand and manufacture on wall surface.				
29.	Carriage of Sand by Mechanical Transport av. Lead with in 55 km upto Tarakote including loading, unloading and stacking properly at site.	CUM	22.31	796.34	17,766.35/-
30.	Carriage of stone aggregate below 40 mm by Mechanical Transport av. Lead within 25 km upto Tarakote including loading, unloading and stacking properly at site.	CUM	5.16	465.14	2400.12/-
31.	Carriage of bricks by MT av. Lead within 60 km upto Tarakote including loading, unloading and stacking properly at site	No.	2708	2.27	6,147.16/-
32.	Carriage of material by M.T Tarakote from Katra to Adhkuwari.	TRIP	46	695	31,970/-
33.	Disposing of dismantled material lading unloading complete.	TRIP	64.78	279.04	18,076.21/-
Total					Rs. 51,21,510.11/-

Sd/-
(Pawan Kumar Goswami, JKAS)
Dy. Chief Executive Officer

No: CO/Dev/703/220
Dated: 07.04.2026



**Office of the Chief Executive Officer
Shri Mata Vaishno Devi Shrine Board, Katra**

**Bill of Quantities (Electrical Works)
(Annexure-B)**

Subject: Renovation of Main Bhojanalya, Prefab Structure for the installing Dumbwaiter in Bhojanalya Building and Re-wiring of Bhojanalya at Adhkuwari.

S. No	Description of Item.	Unit	Qty	Rate (in Rs.)	AMOUNT (in Rs.)
1	WIRING				
a	Wiring for light point / fan point / exhaust fan point / call being point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC Conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq. mm FRLS PVC insulated copper conductor single core cable etc. as required. – Group – C.	NO.	113	1,467	1,65,771/-
b	Wiring for light / power plug with 2 x 2.5 sq. mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit alongwith 1 No. 2.5 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	MTR	240	275	66,000/-
c	Wiring for light power plug with 2 x 4 sq. mm FRLS PVC insulated copper conductor single core cable in surface recessed medium class PVC conduit alongwith 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	MTR	200	334	66,800/-
d	Wiring for circuit / sub main wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface / recessed medium class PVC conduit as required.				
	2 x 2.5 sq. mm + 1 x 2.5 sq. mm earth wire	MTR	240	275	66,000/-
	2 x 6 sq. mm + 1 x 6 sq. mm earth wire	MTR	100	439	43,900/-
e	2 x 10 sq. mm + 1 x 6 sq. mm earth wire	MTR	60	570	34,200/-
	4 x 10 sq. mm + 2 x 6 sq. mm earth wire	MTR	30	1,005	30,150/-
	Supplying and drawing co-axial TV Cable RG -6 grade, 0.7 mm solid copper conductor PE insulated, shielded with fine tinned copper braid and protected with PVC sheath in the existing surface / recessed steel / PVC	MTR	30	47	1,410/-

	conduit as required.				
f	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface / recess including cutting the wall and making good the same in case of recessed conduit as required.				
	25 mm Conduit	MTR	50	145	7,250/-
	32 mm Conduit	MTR	45.75	184	8,418/-
g	Supplying and fixing following modular switch / socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. (Make: - Legrand (Mylinc) / Havell's (Coral))				
	Modular Switch 5/6 Amp.	NO.	24	103	2,472/-
	Modular Switch 15/16 Amp.	NO.	20	156	3,120/-
	Modular Socket 3 pin 5/6 Amp.	NO.	24	122	2,928/-
	Modular Socket 6 pin 15/16 Amp.	NO.	20	197	3,940/-
	TV antenna socket outlet Modular	NO.	1	148	148/-
	Modular Bell Push	NO.	2	140	280/-
h	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc. as required. (Make: - Legrand (Mylinc) / Havell's (Coral))	NO.	16	369	5,904/-
i	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required. (Make: - Legrand (Mylinc) / Havell's (Coral))	NO.	30	40	1,200/-
j	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required. (Make: - Legrand (Mylinc) / Havell's (Coral))				
	1 or 2 Module (75 mmX75 mm)	NO.	1	298	298/-
	3 Module (100 mmX75 mm)	NO.	22	327	7,194/-
	6 Module (200 mmX75 mm)	NO.	12	402	4,824/-
2	MCCB, MCB & DB's				
a	Providing and fixing following capacity TP&N dis-connector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. (Make: - Havell's / ABB / Schinder / Legrand / L&T)				
	100 Amps TP&N	NO.	2	6084	12,168/-
b	Supplying and fixing following way, single pole and neutral , sheet steel, MCB distribution board, 240 V, on surface / recess, complete with tinned copper bus bar, neutral				

	bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCC/Isolator) (Make: - Havell's / ABB / Schinder / Legrand / L&T)				
	8-way, Double door	NO.	2	2573	5,146/-
	12-way, Double door	NO.	2	2315	4,630/-
c	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator). (Make:- Havell's / ABB / Schinder / Legrand/L&T)				
	4 way (4+12), Double door	NO.	2	4091	8,182/-
d	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 KA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. (Make:- Havell's / ABB / Schinder / Legrand/L&T)				
	Single Pole	NO.	32	256	8,192/-
	Single pole and neutral 40 Amp.	NO.	4	599	2,396/-
3	INSTALLATION, TESTING AND COMMISSIONING				
a	Supplying, installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube / lamp etc directly on ceiling / wall, including connections with 1.5 sq. mm FRLS PVC insulated copper conductor, single core cable and earthing etc. as required.				
	LED Tube fitting 14-20 Watt 4 feet long. (Batten 4')	NO.	30	410/-	12,300/-
	LED Tube fitting 10 Watt 2 feet long (Batten 2')	NO.	22	389	8,558/-
	LED Ceiling light 10-12 Watt (Round)	NO.	40	580	23,200/-
	Bell Ding Dong	NO.	2	170	340/-
b	Supplying, Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, including providing and fixing phenolic laminated sheet	NO.	16	2,100/-	33,600/-

	cover on the fan box etc. as required.				
c	Supplying, installation of exhaust fan in the existing opening, including making good the damage, connection, testing, commissioning etc. as required.				
	Upto 450 mm sweep (10")	NO.	2	1,750/-	3,500/-
	Upto 510 mm sweep H/D	NO.	2	4,700	9,400/-
d	Supply, Installation, testing and Commissioning of Geyser 35Ltr etc as required	NO.	2	9,500/-	19,000/-
4	Main Panel				
	Supply, Installation, testing and commissioning of panel 14/16 SWG CRCA fabricated and powder coated, compartmentalized panel with air ventilation and dust/vermin proof.	NO.	1		1,00,000/-
	(A) Main Incoming MCCB				
	a) 200 Amp, 4P, 35 KA MCCB (Make:ABB,Schinder & L&T)	NO.	1		
	b) LED RYB Indicators with MCB Protection (Make:C&S and GE)	Set	1		
	c) Ammeter with switch and voltmeter and frequency meter with switch (Make: AE)	Set	1		
	d) Bus Bars: 200 Amp, 43 Volt, 433 Volt, 4 Strips, Aluminium with heat shrinkable sleeves.	Set	1		
	(B) Outgoing MCCB's				
	a) 100 Amp, 16 KA MCCB 4-Pole. (Make:- ABB/ Schinder and L&T)	NO.	1		
	Total Estimated Cost =				Rs. 7,72,819/-

Sd/-
(Pawan Kumar Goswami, JKAS)
Dy. Chief Executive Officer

No: CO/Dev/703/220
Dated: 07.04.2026



**Office of the Chief Executive Officer
Shri Mata Vaishno Devi Shrine Board, Katra**

**LIST OF PREFERRED MAKES FOR CIVIL WORKS
(Annexure-C)**

Sub: Renovation of Main Bhojanalya, Prefab Structure for the installing Dumbwaiter in Bhojanalya Building and Re-wiring of Bhojanalya at Adhkuwari.

S. No.	Name of Product/ Material	Preferred Brand Names
1	ORDINARY PORTLAND CEMENT (GREY) (43 GRADE)	ACC, ULTRATECH, VIKRAM, SHREE CEMENT, AMBUJA, JAYPEE CEMENT, CENTURY CEMENT & J.K. CEMENT.
2	PORTLAND POZZOLONA CEMENT (GREY) (43 GRADE)	ACC, ULTRATECH, VIKRAM, SHREE CEMENT, AMBUJA, JAYPEE CEMENT, CENTURY CEMENT & J.K. CEMENT.
3	WHITE CEMENT	J.K.WHITE, JAIPUR SUPREME PACKAGING PVT. LTD., ULTRATECH CEMENT LIMITED.
4	REINFORCEMENT STEEL	SAIL, TATA STEEL LTD., RINL, JINDAL STEEL & POWER LTD. AND JSW STEEL LTD.
5	ADMIXTURES	CICO, FAIRMATE, HIND PLAST SUPER, SUPAPLAST, SIKA
6	WATER PROOFING COMPOUND	FOSROC, CICO, KRYTON, BUILDMATE, PIDLITE, PRIYA ENTERPRISES, FAIRMATE, SIKA
7	READY MIX CONCRETE	M/S L&T CONCRETE (LAFARGE), ULTRATECH CEMENT LTD., ACC CONCRETE LTD., RMC READY MIX (INDIA) PVT. LTD.
8	AUTOCLAVED AERATED BLOCKS	BILTECH, ECO GREEN, FINECRETE, J.K. LAKSHMI CEMENT LTD.
9	POLYMER MODIFIED ADHESIVE FOR AAC BLOCKS	MYK LATICRETE, FERROUS CRETE, ARDEX ENDURA, ULTRATECH, SIKA.
10	FACTORY MADE PANELLED & WIRE GAUGE WOODEN DOOR/ WINDOW SHUTTERS.	M/S JAIN WOOD INDUSTRIES, KUTTY DOORS, SAMRAT PLYWOOD, NEW JAGDAMBA DOORS, MERINO, KITPLY, AS TIMBER, JAIN DOORS PVT. LTD.
11	FLUSH DOOR SHUTTERS	KUTTY FLUSH DOOR, SAMRAT LAMINATE, NATIONAL PLYWOODS, JAIN WOOD INDUSTRIES, MERINO, MINIMAX, CENTURY, AS TIMBER. ORION, JAIN DOORS PVT. LTD.
12	BLOCK BOARD	MERINO, MINIMAX, NATIONAL,

		ARCHIDPLY, CENT PLY, JAYNA, CENTURY.
13	LAMINATES	SAMRAT, VIRGO, MERINO, ARCHIDPLY, CENTURY LAMINATES, GREENLAM
14	PRE-LAMINATED PARTICLE BOARD	ARCHIDPLY, CENTURY PLY BOARDS, BALAJI ACTION BUILDWELL, ECOBOARD
15	PARTICLE BOARD (MEDIUM DENSITY)/ VENEERED PARTICLE BOARD	CENTURY PLYBOARDS (INDIAN) LTD., BALAJI ACTION BUILDWELL, EVERGREEN BOARDLAM, ECOBOARD INDUSTRIES LTD.
16	PRE-LAMINATED MEDIUM DENSITY FIBRE BOARD	CENTURY PLYBOARDS, GREEN PLY, BALAJI ACTION BUILDWELL
17	OMS/ MS DOOR FITTINGS	ASHISH, AGGARWAL STEELS, DOOR DEVICES MANUFACTURING COMPANY, MANU ENGINEERING COMPANY, M.C. MOWJEE & CO., SHRI GANPATI DOORS
18	TOILET CUBICALS	GREELAM, MERINO, DORMA
19	STAINLESS STEEL DOOR/WINDOW HARDWARE FITTINGS (FIRE RATED AND NON-FIRE RATED)	DORMA, ASSA ABLOY, GEZE, D-LINE
(i)	FIRE RATED BALL BEARING HINGES OF STEEL GRADE SS304	GEZEMODEL NO. 98850001 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(ii)	FIRE RATED DEAD LOCK BOTH SIDE KEY OPERATION	GEZE MODEL NO. 98484002 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(iii)	PANIC BAR 1&2 POINT LOCKING PANIC BOLT (DOOR Ht. UPTO 2400MM)	GEZE MODEL NO. 98536301 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(iv)	EXTERNAL TRIM WITH LEVER HANDLE	GEZE MODEL NO. 98536302 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(v)	AUTOMATIC DOOR METAL SEAL	GEZEMODEL NO. 98427392 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(vi)	SURFACE MOUNTED RACK&PINION FIRE RATED DOOR CLOSER (DOOR WT. 100 KG)	GEZE MODEL NO. 1010008 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(vii)	PULL HANDLE BACK TO BACK, LENGTH 300MM OF STEEL GRADE SS 304	GEZE MODEL NO. 98163135 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(viii)	FLOOR STOPPER OF HALF DOME OF 45MM DIA OF STEEL GRADE SS 304	GEZE MODEL NO. 98487003 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(ix)	LEVER HANDLE IN SS 304 FINISH	GEZEMODEL NO. 98482004 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE

(x)	GRAB BAR OF LENGTH 610MM, 25MM DIA	GEZE MODEL NO. 98163011 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(xi)	SURFACE MOUNTED RACK & PINION DOOR CLOSER	GEZE MODEL NO. 1010001 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(xii)	KICK PLATE 0.9MM THICKNESS IN SS 304 FINISH	GEZE MODEL NO. 98167014 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(xiii)	FIRE SEAL	DORMA RP55 OR EQUIVALENT MODEL OF ASSA ABLOY, GEZEMODEL NO. 98427392, D-LINE, GODREJ
(xiv)	PUSH PLATE IN SS 304 GRADE	DORMA MODEL NO. 1100 OR EQUIVALENT MODEL OF ASSA ABLOY, GEZE, D-LINE, GODREJ
(xv)	DUST EXCLUDING SOCKET IN SS 304 GRADE	DORMA 3/24 OR EQUIVALENT MODEL OF ASSA ABLOY, GEZEMODEL NO. 98487007, D-LINE, GODREJ
(xvi)	LEVER ACTION FLUSH BOLT 300MM LENGTH	GEZE MODEL NO. 98307012 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(xvii)	BALL BEARING HINGES HAVING 5 KNUCKLE	GEZE MODEL NO. 98850001 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(xviii)	DEAD LOCK WITH 55MM BASKET IN SS 304	GEZE MODEL NO. 98344021 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(xix)	DISABLE/ MALE/ FEMALE SIGN PLATE IN SS 304	GEZE MODEL NO. 8167003M,8167004F,8167005D OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE
(xx)	AUTOMATIC SLIDING GLASSDOOR	DORMA ES200 OR EQUIVALENT MODEL OF ASSA ABLOY, GEZE, D-LINE.
(xxi)	FLOOR SPRINGS SATIN STAINLESS STEEL	GEZE MODEL NO. 1740004,1740002 OR EQUIVALENT MODEL OF DORMA, ASSA ABLOY, D-LINE.
20	ANODISED/ ZINC ALLOY/ ALUMINIUM HARDWARE DOOR/ WINDOW FITTINGS	PULSE, SAVIO, HOPPE, ALUTECH
21	FRP DOOR FRAMES & SHUTTERS	ASHISH INDUSTRIES, JAYNA, SAINIK (CENTURY PLYWOOD), SELECTED PRODUCTS CO., JAIN DOORS PVT. LTD.
22	UPVC WINDOWS/ DOORS	VEKA, FENESTA, REHAU,PROMINANCE WINDOW SYSTEM, ALUPLAST , ENCRAFT.
23	UPVC WINDOW/ DOOR HARDWARE FITTINGS (ZINC ALLOY)	PULSE, HOPPE, GU, ROTO, GODREJ, KINLONG
24	WIDOWS BLINDS	VISTA, MAC, HUNTER, DOUGLAS, DE-DÉCOR

25	STRUCTURAL STEEL SUCH AS MS FLATS, SQ.BARS ANGLES ETC.	SAIL, TATA STEEL, RINL, JINDAL STEEL & POWER LTD. AND JSW STEEL LTD.
26	FIRE RATED DOORS (METTALIC/ NON METTALIC)	KUTTY DOORS, NAVAIR, PROMAT, SYNERGY THRISLINGTON , JAIN DOORS PVT. LTD.
27	HOT-ROLLED STEEL SECTIONS FOR MS DOORS, WINDOWS AND VENTILATORS	NAV DURGA STEEL CORPN, CRM STEELS P. LTD, SHYAM ISPAT UDYOG, VIMAL, SHIV
28	MILD STEEL DOOR, WINDOWS & VENTILATORS MANUFACTURERS	FRIENDS MANUFACTURING COMPANY, KOTKAPURA, PD INDUSTRIES, SHAKTI INDUSTRIES, STEELMAN INDUSTRIES, SKS STEEL INDUSTRIES, SHIVAM
29	PRESSED STEEL DOOR FRAMES MANUFACTURERS	KRISHNA STEEL FABRICATOR SIRSA, LAXMI STEEL WORKS BAHADURGARH, ASHISH INDUSTRIES GHAZIABAD, ASHWANI & SONS, SHRI GANPATI DOORS
30	HOLLOW STEEL SECTIONS	JINDAL INDUSTRIES HISAR, TATA STEEL, STEEL & METAL TUBES (INDIA) PVT.LTD.
31	STEEL TUBES FOR STRUCTURAL STEEL	JINDAL INDUSTRIES HISAR, TATA STEEL, STEEL & METAL TUBES (INDIA) PVT. LTD.
32	DASH/ ANCHORING FASTENERS, BOLTS, SCREWS AND NUTS.	HILTI , FISCHER, CKW, ATUL, PRIYA
33	STAINLESS STEEL RAILING	DORMA, KICH, OM STEEL , D-LINE.
34	CHEQUERRED PRE-CAST CC TILES	NTC, SWASTIK TILE, POOJA CONCRETE FABRICATORS, GTC.
35	CERAMIC TILES	SOMANY, KAJARIA, ORIENTBELL, RAK, ASIAN GRANITO INDIA LTD.
36	VITRIFIED TILES	SOMANY, KAJARIA,ORIENTBELL, RAK, ASIAN GRANITO INDIA LTD.
37	ADHESIVE/ GROUTING FOR USE WITH TILES	FERROUS CRETE, MYK LATICRETE, ARDEX EDURA, FAIRMATE, DURA BUILD CARE, SIKKA
38	WOODEN LAMINATE FLOORING	PERGO, KRONOTEX, FLORENCE, UNITEX, ACTION TESA
39	UNPLASTICISED RIGID PVC PIPE & FITTINGS	SUPREME, FINOLEX, PRINCE, KISAN, DIPLAST.
40	GALVANISED STEEL SHEETS (UNCOATED & PRE-COATED)	SAIL, TATA, JINDAL, NCL
41	ROOFING SHEETS (GALVALUME)	CRIL, LLOYDS, INTERACH, MULTICOLOR, BHUSHAN POWER STEEL
42	FALSE CEILING- GYPSUM	SAINT GOBAIN, VANS GYPSUM, USG BORAL, LLYOD
43	FALSE CEILING- METAL	ARMSTRONG, DEXUNE, SAINT GOBAIN, HUNTER DOUGLAS, GYPTECH

44	FALSE CEILING- CALCIUM SILICATE	HILUX, AEROLITE, ARMSTRONG, PROLAD
45	FALSE CEILING-MINERAL FIBRE	ARMSTRONG, DEIKEN, DEXUNE, SAINT GOBAIN, PROLAD
46	ACCOUSTIC: GLASS / WOODEN FIBRE FALSE CEILING AND WOODEN/ FABRIC WALL LINING	ARMSTRONG, DEXUNE, ACCOUSTIBLOK, HIMALYAN ACOUSTICS, ANUTONE, GYPTECH, PROLAD
47	FALSE CEILING-ALUMINIUM POWDER COATED	ARMSTRONG, DEXUNE, SAINT GOBAIN, HUNTER DOUGLAS
48	LIGHT WEIGHT GYPSUM PLASTER	SAINTE GOBAIN, ULTRATECH, FERROUS CRETE, USG BORAL.
49	OIL BOUND DISTEMPER/ ACRYLIC DISTEMPER *	NEROLAC ACRYLIC DISTEMPER, TRACTOR ACRYLIC DISTEMPER (ASIAN PAINTS), MAXILITE ACRYLIC DISTEMPER (ICI), BISON ACRYLIC DISTEMPER (BERGER).
50	INTERIOR EMULSION/ PLASTIC EMULSION*	DULUX ACRYLIC EMULSION/ SOLITAIRE A-1000 (ICI), APCOLITE PREMIMUM EMULSION (ASIAN), BEAUTY GOLD (NEROLAC), SILK (BERGER)
51	ACRYLIC SMOOTH EXTERIOR PAINT*	APEX ULTIMA (ASIAN), DULUX WEATHERSHEILD MAX (ICI), EXCEL (NEROLAC), WEATHERCOAT ALL GUARD (BERGER)
52	DRY DISTEMPER*	NEROLAC, BERGER, ASIAN PAINTS, ICI, JENSON & NICHOLSON (J&N)
53	TEXTURED EXTERIOR PAINT*	NEROLAC, BERGER, ASIAN PAINTS, ICI
54	SYNTHETIC ENAMEL PAINTS*	DULUX HI-GLOSS (ICI), APCOLITE PREMIMUM GLOSS (ASIAN), NEROLAC HIGH GLOSS (NEROLAC), LUXOL HI-GLOSS (BERGER)
55	WOOD PRIMER*	NEROLAC, BERGER, ASIAN PAINTS, ICI
56	STEEL PRIMER*	NEROLAC, BERGER, ASIAN PAINTS, ICI
57	EXTERIOR WALL PRIMER*	EXTERIOR NEROLAC PRIMER, EXTERIOR BERGER PRIMER, EXTERIOR ASIAN PAINTS PRIMER, EXTERIOR ICI PRIMER
58	WALL PUTTY (WHITE CEMENT BASED)	BIRLA WALL CARE, JK WHITE, SARA WALL PUTTY
59	POLYMER MODIFIED SELF CURING PLASTER	MYK LATICRETE, FERROUS CRETE, ARDEX ENDURA, ULTRATECH
60	PAVER/ GRASS PAVER BLOCKS & KERB STONES	NATIONAL TILES CORPORATION, SARAL IMPEX, BALAJI TILES, METRO PAVERS, MGM INFRA, KRISHNA TILES, POOJA CONCRETE FABRICATORS, GIAN NIRMAN LIMITED, A-1 TILES
61	VITREOUS CHINA SANITARY WARE	HINDWARE, CERA, PARRYWARE, JOHNSON PEDDER, SOMANY.
(I)	WHITE VITREOUS CHINA	CERA CAT. NO. S 2030104 OR

	UNDER COUNTER RECTANGULAR BASIN	EQUIVALENT MODEL OF HINDWARE, PARRYWARE, JOHNSON PEDDER, SOMANY
62	PLASTIC FLUSHING CISTERN FOR WC AND URINALS	JINDAL, STEEL BIRD, SEEMLINE, VIKRAM PLASTIC, PRAYAG POLYMERS (P) LTD.
63	PLASTIC SEAT COVER OF W.C.	AJANTA POLYMERS, JINDAL MALPINE, JAIN POLYMERS
64	STAINLESS STEEL SINK	ALLEX, JAYNA, JMD INTERNATIONAL, STEEL CRAFT
65	MIRROR GLASS	ATUL, MODIGUARD, GOLDEN FISH
66	CENTRIFUGALLY CAST (SPUN) IRON PIPES	NECO, BENGAL IRON, DURGAPUR ISPAT UDYOG, SINGHAL IRON FOUNDRY (SKF), KAPILANSH DHATU UDYOG PVT. LTD., RPFM, HIF.
67	HUBLESS CENTRIFUGALLY CAST (SPUN) IRON PIPES	NECO, RAJ PATTERN MAKERS & FOUNDERS, SINGHAL IRON FOUNDRY (SKF).
68	CP FITTINGS & ACCESSORIES	JAQUAR, HINDWARE, PRIMA, JAINKO, CERA, JAL
(i)	CP Brass Health Faucet 15 mm N.B.	CERA Cat. No. F8030301 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(ii)	CP Brass Auto closing pillar cock 15 mm	CERA Cat. No. F9020101 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(iii)	CP Brass sink mixer 15 mm	CERA Cat. No. F2002511 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(iv)	CP Brass towel rail 600mm long	CERA Cat. No. F5004103 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(v)	CP Brass towel ring	CERA Cat. No. F5002105 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(vi)	CP Brass shower with shower arm 450mm	CERA Cat. No. F7040106 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(vii)	Liquid soap dispenser with CP Brass holder and glass bottle of 300ml capacity	CERA Cat. No. F5007111 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(viii)	CP Brass wall mixer 15 mm	CERA Cat. No. F3002401 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(ix)	CP BRASS BIB COCK 15mm NB	CERA Cat. No. F2002151 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(x)	CP BRASS LONG NOSE BIB COCK 15mm NB	CERA Cat. No. F2002152 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(xi)	CP BRASS LONG BODY BIB	CERA Cat. No. F3002152 OR EQUIVALENT

	COCK 15mm NB	MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
(xii)	CP BRASS ANGL VALVE 15mm NB	CERA Cat. No. F2002201 OR EQUIVALENT MODEL OF JAQUAR, HINDWARE, JAINKO, PRIMA, JAL
69	BRASS STOP & BIB COCK	DHAWAN SANITARY UDYOG, JAINKO, SHAKTI, VARDHMAN INDIA PRODUCTS
70	FERRULES FOR WATER SUPPLY	HIND METAL WORKS, KRITIKA, DRP, SHAKTI
71	BALL COCK WITH ROD	RESP FAUCET INDUSTRIES, DHAWAN SANITARY UDYOG, NEW METAL WORKS, KPR, PRAYAG.
72	POLYETHYLENE WATER STORAGE TANK	SINTEX, VECTUS, KAVERI
73	STONEWARE PIPES & GULLY TRAPS	SORKHI INDUSTRIES, RK INDUSTRIES, NAVNEET, MOLI CERAMICS, OCR, ANAND
74	PRE-CAST CONCRETE PIPES (NON-PRESSURE)	RAMNIK, BFSP, JAGDAMBAY SPUN PIPE, GURKIRPA SPUN PIPES
75	GI PIPE	JINDAL (HISSAR), TATA, BST, BHUSHAN POWER STEEL
76	GI FITTINGS	UNIK, AVR, ZOLOTO, SANT, HBI, C-BRAND, NVR
77	C-PVC PIPE	PRINCE, JINDAL (FLOWKEM), ASTRAL, AJAY POLYMERS, SUPREME, FINOLEX, JAIN PIPES
78	WATER METER	CRESCENT, PRINCE, FEDREL, DASHMESH, NBESON, SANT
79	GUN METAL GATE, GLOBE, CHECK VALVES & NON-RETURN VALVES	LEADER, ZOLOTO, SANT, RAJAN METAL INDUSTRIES, SIR, H.B. METALS, HVI, NVR.
80	CENTRIFUGALLY CAST (SPUN) IRON PIPES (CLASS LA).	TRU FORM ENGINEERS, KAPILANSH, ELECTROSTEEL, HITECH METAL CASTINGS.
81	C.I. SLUICE VALVES & REFLEX VALVES	ZOLOTO INDUSTRIES, SANT VALVES, AMCO INDUSTRIES, KIRLOSKAR, SIR, RATAN INDUSTRIAL CORPORATION, HVI, NVR.
82	STAINLESS STEEL PIPES & FITTINGS	JINDAL STAINLESS STEEL, OM STEEL GROUP, V STEEL, VIEGA, RAMPART INDIA PVT. LTD.,
83	DUCTILE IRON PIPES & FITTINGS	JINDAL SAW LTD, ELECTRO STEEL, CHANDRANCHAL INFRA, ELECTROTHERAM
84	C.I./ D.I. MANHOLE COVERS & FRAMES	SWASTIKA ENTERPRISES, BENGAL IRON CORPORATION, NECO, BINAY UDYOG, CHANDERANCHAL
85	WATER REPELLANT SILANE CHEMICAL	PIDILITE, FERROUS CRETE, ARDEX ENDURA
86	ALUMINIUM SECTIONS	HINDALCO, JINDAL, INDIAN ALUMINIUM CO.

87	BASIC/ TOUGHENED ETC. GLASS	SAINT GOBAIN, ASAHI, MODI, GOLD PLUS GLASS, PILINGTON.
88	APPROVED PROCESSORS FOR PERFORMANCE GLASS/ TOUGHENED GLASS/ HERMETICALLY SEALED/ LACQUERED GLASS etc.	ART & GLASS, MIRAGE TOUGHENED GLASSES (P) LTD., AAR PAR GLASS, VERMA GLASS.
89	STRUCTURAL GLAZING	ALCOB, ALUPRO, ALUPLAX, SP FABRICATORS, SAINT GOBAIN, GLAVERBEL.
90	FAÇADE GLASS OPENABLE FITTINGS	ALUALPHA, SAVIO, HOPPE, ALUTECH
91	GLASS FAÇADE/ GLASS CANOPY WITH SS SPIDER FITTINGS	ALCOB, ALUPRO, ALUPLAX, SP FABRICATORS, SAINT GOBAIN, GLAVERBEL.
92	FRAMELESS GLAZING WITH SS PATCH FITTINGS	DORMA, ASSA ABLOY, GEZE, D-LINE
93	AC PIPES (Mazza)	A INFRASTRUCTURE LTD., APURVA VINIMAY PVT. LTD., KANORIA SUGAR GEN. MFG. CO. LTD.
94.	PRECOATED/PREPAINTED GALVANIDE ROLLED FORMED STEEL DOORS, WINDOWS, AND VENTILATORS FRAMES	NCL BUILDTECH LIMITED, MADHU INDUSTRIES SANHARBIC, ELIXIR MET FORM

*Batch test certificate of paints and primer shall be supplied alongwith each lot.

Sd/-
(Pawan Kumar Goswami, JKAS)
Dy. Chief Executive Officer

No: CO/Dev/703/220
Dated: 07.04.2026



**Office of the Chief Executive Officer
Shri Mata Vaishno Devi Shrine Board, Katra**

**LIST OF PREFERRED MAKES FOR ELECTRICAL WORKS
(Annexure-D)**

**Subject: Renovation of Main Bhojanalya, Prefab Structure for the installing
Dumbwaiter in Bhojanalya Building and Re-wiring of Bhojanalya at
Adhkuwari.**

Sr.No.	Name of Product/ Material	Preferred Brand Names
1	FRLS PVC Copper Wires	Havell's/ Polycab/ KEI
2	XLPE Cable's / PVC Al. Steel 3.5 Core Cables Armored.	Havell's/ Polycab/ KEI
3	PVC Conduit Pipes 2" Thick	National Gold, Poly Plast, Hi power & Plaza
4	PVC Bends 2" Thick	National Gold, Poly Plast, Hi power & Plaza
5	Piano type Switch, Sockets, Bell Switch, etc.	Havell's/ Anchor / Gratewhite
6	TPN DB's Double door	ABB/Schinder & L&T
7	SPN DB Double Door	ABB/Schinder & L&T
8	MCB (C-Curve)	ABB/Schinder & L&T
9	SPN (C-Curve)	ABB/Schinder & L&T
10	Led Surface Mounted Ceiling light 12 / 10 Watt	Osram / Wipro / Philips / Havell's & Syska
11	LED Tube Fitting 14/20 Watt 4 feet long (Batten)	Osram / Wipro / Philips / Havell's & Syska
12	LED Tube Fitting 4/5 Watt 1 feet long (Batten)	Osram / Wipro / Philips / Havell's & Syska
13	LED Lamps	Osram / Wipro / Philips / Havell's & Syska
14	Led Glove 8"	Osram / Wipro / Philips / Havell's & Syska
15	IP 57 Pole Box	Hansel

**Sd/-
(Pawan Kumar Goswami, JKAS)
Dy. Chief Executive Officer**

**No: CO/Dev/703/220
Dated: 07.04.2026**

CHECK LIST
(Technical Bid Qualification)

S.No.	DOCUMENTS	SUBMITTED	
		YES	NO
1.	Tender fee and EMD		
2.	Copies of original documents defining the constitution or legal status, place of registration and principal place of business.		
3.	Financial turnover Certificate, year-wise, for the last three Financial Years i.e. 2022-23 to 2024-25 , duly certified by the Chartered Accountant		
4.	Work Completion Certificates along with Letter of Awards of having executed and completed successfully works of similar nature as defined under Clause 3 of the Technical Eligibility Criteria, in any Govt. or Semi- Govt. Departments / Govt. PSU's / Autonomous Bodies during the last five years, duly issued by an officer not below the rank of Executive Engineer or equivalent		
5.	Copy of PAN Card and GST registration certificate and valid Contractor Registration Card issued from the Competent Authority.		
6.	Reports on financial standing of the bidder such as profit and loss statement, balance sheet for the last three Financial Years i.e. 2022-23 to 2024-25 , duly certified by Chartered Accountant and supported with ITRs of the last three Financial Years		
7.	Proof of latest returns in GST-3/GSTR-3B.		
8.	Signed and Stamped copy of Tender document (all pages) in respect of acceptance of all terms and conditions of e-NIT.		

Authorized Signatory of the firm